



NOTES:

1. ALL DETAILS AND SPECIFICATIONS FOR "STANDARD PRECAST MANHOLE" (DETAIL SLWS-05) ARE APPLICABLE.
2. A DROP CONNECTION IS REQUIRED WHENEVER AN INFLUENT INVERT IS LOCATED 2' OR HIGHER THAN THE MAIN INVERT CHANNEL. MANHOLES WITH A DROP 2.0 FEET OR LESS SHALL BE IN ACCORDANCE WITH DETAIL SLWS-05.
3. ALL MATERIALS AND COMPONENTS USED SHALL BE PER SLWSD QUALIFIED PRODUCTS LIST.
4. PVC SDR 26 PIPE WITH PVC SDR 26 FITTINGS SHALL BE UTILIZED IN THE DROP ASSEMBLY.
5. THE DROP ASSEMBLY SHALL BE ATTACHED TO THE MANHOLE WALL WITH MINIMUM 1 1/2", 16 GAUGE STAINLESS STEEL STRAPS AT EACH JOINT IN THE ASSEMBLY USING 3/8"X4" STAINLESS STEEL EXPANSION ANCHORS.



MINIMUM CONSTRUCTION STANDARDS FOR
 ST. LUCIE WEST SERVICES DISTRICT
 450 SW UTILITY DRIVE,
 PORT SAINT LUCIE, FL 34986
 PHONE: (772) 340-0220

**INSIDE DROP CONNECTION
 PRECAST MANHOLE**

DETAIL: SLWS-09
DATE: 03/2020
SCALE: N.T.S.
SHEET: 1 OF 1